



EO WORKBOATS FRSV - Crew vessel

Fast Response Support Vessel

Ready for delivery within three months.

Brand: Alunautic

Model: Deep V hull—14.00 FRSV—Crew boat

Building year: 2020

Crew transport—coastal control

Lloyds approved for drawing and welding.

Final approval: MCA 280 MGM—60 NM

SPECIFICATIONS:

Hull: Marine Grade Aluminium

Fender: Foam filled PU finished.

Dimensions:

Length: l.o.a.: 14.00 m

Beam o.a.: 4.10 m

Dept at side: 0.85 m

Draught app: 0.95 m

Gross tonnage / Nett tonnage approx.: 9 / 7 Ton

Capacity :

Fuel: 2 x 600 L

Crew: 2 @ suspended seats.

Passengers: 11 persons suspended seating (we can make another arrangement for more pax capacity.

Performance:

Max speed: Approx 33 Knots

Range: 375 NM

Propulsion system:

Engine: Twin Volvo Penta D3 300 - twin Volvo Stern drive

Auxiliary equipment:

Basic E-system with 4 batteries and battery switches— shore power 12– 230 Volt plus charger.

Hydraulic steering: Seastar.

Fire pro in engine room.

Twin Dometic AC roof units with diesel generator.

Deck layout:

Deck is self draining.

Deck: Aluminium diamond plate.

Lifting eyes : 4 pcs.

Mast with navigation lighting, antenna, radar

Nautical and communication equipment:

Raymarine echo sounder, GPS, Radar, AIS.

Raymarine VHF Radio 2 x plus handheld VHF radio.

MF/HF radio.

Navtex receiver,

SART transponder, GMDSS approved

EPIRB. GMDSS approved

Various:

Search light roof unit with remote control.

Deck crane;

Cabin with toilet and sink, bed and desk.

Electrical anchor winch with anchor, chain and line

Fire extinguishers.

Swimming ladder

Superstructure coated in orange with 2 component UC2K glass coat with 10 years UV protection. Under water hull coated.



EO WORKBOATS FRSV - Crew vessel
Fast Response Support Vessel

